

AD-A156 388


NATIONAL PROGRAM FOR INSPECTION OF NON-FEDERAL DAMS  
PAPER MILL DAM (NH 00.) (U) CORPS OF ENGINEERS WALTHAM  
MA NEW ENGLAND DIV FEB 79


1/1

UNCLASSIFIED

F/G 13/13

NL





NATIONAL BUREAU OF STANDARDS  
MICROCOPY RESOLUTION TEST CHART

AD-A156 388

MERRIMACK RIVER BASIN  
BENNINGTON, NEW HAMPSHIRE

PAPER MILL DAM  
NH 00251

STATE NO 22.06

PHASE I INSPECTION REPORT  
NATIONAL DAM INSPECTION PROGRAM



DTIC  
SEC  
JUL 09 1985  
G

DEPARTMENT OF THE ARMY  
NEW ENGLAND DIVISION, CORPS OF ENGINEERS  
WALTHAM, MASS. 02154

FEBRUARY 1979

DTIC  
Approved for Release by NSA  
Distribution Unlimited

85 06 18 122

OTIC FILE COPY

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER NH 00251	2. GOVT ACCESSION NO. <b>A156388</b>	3. RECIPIENT'S CATALOG NUMBER
4. TITLE (and Subtitle) Paper Mill Dam NATIONAL PROGRAM FOR INSPECTION OF NON-FEDERAL DAMS		5. TYPE OF REPORT & PERIOD COVERED INSPECTION REPORT
7. AUTHOR(s) U.S. ARMY CORPS OF ENGINEERS NEW ENGLAND DIVISION		6. PERFORMING ORG. REPORT NUMBER
9. PERFORMING ORGANIZATION NAME AND ADDRESS		8. CONTRACT OR GRANT NUMBER(s)
11. CONTROLLING OFFICE NAME AND ADDRESS DEPT. OF THE ARMY, CORPS OF ENGINEERS NEW ENGLAND DIVISION, NEDED 424 TRAPELO ROAD, WALTHAM, MA. 02254		10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office)		12. REPORT DATE February 1979
		13. NUMBER OF PAGES 45
		15. SECURITY CLASS. (of this report) UNCLASSIFIED
		15a. DECLASSIFICATION/DOWNGRADING SCHEDULE
16. DISTRIBUTION STATEMENT (of this Report) APPROVAL FOR PUBLIC RELEASE: DISTRIBUTION UNLIMITED		
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report)		
18. SUPPLEMENTARY NOTES Cover program reads: Phase I Inspection Report, National Dam Inspection Program; however, the official title of the program is: National Program for Inspection of Non-Federal Dams; use cover date for date of report.		
19. KEY WORDS (Continue on reverse side if necessary and identify by block number) DAMS, INSPECTION, DAM SAFETY, Merrimack River Basin Bennington, New Hampshire Contoocook River		
20. ABSTRACT (Continue on reverse side if necessary and identify by block number) The dam has a hydraulic height of 13 ft. and is 280 ft. long. It is a run of the river concrete gravity dam with a spillway length of 142 ft. The dam is in fair condition with a few major concerns. It is small in size with a significant hazard classification. A major breach at top of dam would result in the loss of few, if any lives and appreciable property damage.		

## **DISCLAIMER NOTICE**

**THIS DOCUMENT IS BEST QUALITY  
PRACTICABLE. THE COPY FURNISHED  
TO DTIC CONTAINED A SIGNIFICANT  
NUMBER OF PAGES WHICH DO NOT  
REPRODUCE LEGIBLY.**



DEPARTMENT OF THE ARMY  
NEW ENGLAND DIVISION, CORPS OF ENGINEERS  
424 TRAPELO ROAD  
WALTHAM, MASSACHUSETTS 02154

REPLY TO  
ATTENTION OF:  
NEDED

FEB 14 1980

Honorable Hugh J. Gallen  
Governor of the State of New Hampshire  
State House  
Concord, New Hampshire 03301

Dear Governor Gallen:

Inclosed is a copy of the Paper Mill Dam Phase I Inspection Report, which was prepared under the National Program for Inspection of Non-Federal Dams. This report is presented for your use and is based upon a visual inspection, a review of the past performance and a brief hydrological study of the dam. A brief assessment is included at the beginning of the report. I have approved the report and support the findings and recommendations described in Section 7 and ask that you keep me informed of the actions taken to implement them. This follow-up action is a vitally important part of this program.

A copy of this report has been forwarded to the Water Resources Board, the cooperating agency for the State of New Hampshire. In addition, a copy of the report has also been furnished the owner, Monadnock Paper Mills, Bennington, New Hampshire.

Copies of this report will be made available to the public, upon request, by this office under the Freedom of Information Act. In the case of this report the release date will be thirty days from the date of this letter.

I wish to take this opportunity to thank you and the Water Resources Board for your cooperation in carrying out this program.

Sincerely,

*Max B. Scheider*

MAX B. SCHEIDER  
Colonel, Corps of Engineers  
Division Engineer

Incl  
As stated



Acc	
ADM	
ENG	
PLN	
Proc	
Just	
Per	
Pr	

✓

A/S

NATIONAL DAM INSPECTION PROGRAM  
PHASE I INSPECTION REPORT

Identification No.: NH00251  
Name of Dam: Paper Mill Dam  
Town: Bennington  
County and State: Hillsborough County, New Hampshire  
River: Contoocook River  
Date of Inspection: November 20, 1978


BRIEF ASSESSMENT

Paper Mill Dam has a hydraulic height of 13 feet, is of varied topwidth, and totals 280 feet long. It is a run-of-the-river concrete gravity dam with a spillway length of 142 feet. The spillway has a 45° inclined downstream face. The head and waste gates are located in the north abutment. The dam spans a reach of the Contoocook River, and is located in south-central New Hampshire. Maximum storage capacity is about 50 acre-feet. Paper Mill Dam is used for industrial process water as well as for hydropower purposes. The pond is about 1140 feet in length with a surface area of about 5 acres.


The dam is in fair condition. Major concerns are: structural stability of the spillway under conditions of the test flood and the deteriorated concrete in the dam and gate structures.


Based on small size and significant hazard classifications in accordance with Corps guidelines, the test flood is 1/4 Probable Maximum Flood (PMF). A test flood outflow of 15,760 cfs (83 csm) would overtop the dam by about 5.2 feet (9.1 feet over spillway crest). The spillway will pass 3,830 cfs or about 24 percent of the test flood. A major breach at top of dam would result in the loss of few, if any lives and appreciable property damage.


The owner, Monadnock Paper Mills, should implement the results of the recommendations and remedial measures given in Sections 7.2 and 7.3 within one year after receipt of this Phase I inspection report.

  
Warren A. Guinan  
Project Manager  
N.H. P.E. 2339

This Phase I Inspection Report on Paper Mill Dam has been reviewed by the undersigned Review Board members. In our opinion, the reported findings, conclusions, and recommendations are consistent with the Recommended Guidelines for Safety Inspection of Dams, and with good engineering judgement and practice, and is hereby submitted for approval.

  
JOSEPH W. FINEGAN, JR., MEMBER  
Water Control Branch  
Engineering Division

  
CARNEY M. TERZIAN, MEMBER  
Design Branch  
Engineering Division

  
JOSEPH A. MCELROY, CHAIRMAN  
Chief, NED Materials Testing Lab.  
Foundations & Materials Branch  
Engineering Division

APPROVAL RECOMMENDED:

  
JOE B. FRYAR  
Chief, Engineering Division



## PREFACE

This report is prepared under guidance contained in the Recommended Guidelines for Safety Inspection of Dams, for Phase I Investigations. Copies of these guidelines may be obtained from the Office of Chief of Engineers, Washington, D.C. 20314. The purpose of a Phase I Investigation is to identify expeditiously those dams which may pose hazards to human life or property. The assessment of the general condition of the dam is based upon available data and visual inspections. Detailed investigation and analyses involving topographic mapping, subsurface investigations, testing, and detailed computational evaluations are beyond the scope of a Phase I investigation; however, the investigation is intended to identify any need for such studies.

In reviewing this report, it should be realized that the reported condition of the dam is based on observations of field conditions at the time of inspection along with data available to the inspection team. In cases where the reservoir was lowered or drained prior to inspection, such action, while improving the stability and safety of the dam, removes the normal load on the structure and may obscure certain conditions which might otherwise be detectable if inspected under the normal operating environment of the structure.

It is important to note that the condition of a dam depends on numerous and constantly changing internal and external conditions, and is evolutionary in nature. It would be incorrect to assume that the present condition of the dam will continue to represent the condition of the dam at some point in the future. Only through continued care and inspection can there be any chance that unsafe conditions be detected.

Phase I inspections are not intended to provide detailed hydrologic and hydraulic analyses. In accordance with the established Guidelines, the Spillway Test flood is based on the estimated "Probable Maximum Flood" for the region (greatest reasonably possible storm runoff), or fractions thereof. Because of the magnitude and rarity of such a storm event, a finding that a spillway will not pass the test flood should not be interpreted as necessarily posing a highly inadequate condition. The test flood provides a measure of relative spillway capacity and serves as an aide in determining the need for more detailed hydrologic and hydraulic studies, considering the size of the dam, its general condition and the downstream damage potential.

## TABLE OF CONTENTS

Title	Page
LETTER OF TRANSMITTAL.....	
BRIEF ASSESSMENT.....	
REVIEW BOARD PAGE.....	
PREFACE.....	iv
TABLE OF CONTENTS.....	v
OVERVIEW PHOTO.....	vi
LOCATION MAP.....	vii

### REPORT

#### Section

1	PROJECT INFORMATION.....	1-1
	1.1 General.....	1-1
	1.2 Description of Project.....	1-1
	1.3 Pertinent Data.....	1-3
2	ENGINEERING DATA.....	2-1
	2.1 Design.....	2-1
	2.2 Construction.....	2-1
	2.3 Operation.....	2-1
	2.4 Evaluation.....	2-1
3	VISUAL INSPECTION.....	3-1
	3.1 Findings.....	3-1
	3.2 Evaluation.....	3-3
4	OPERATIONAL PROCEDURES.....	4-1
	4.1 Procedures.....	4-1
	4.2 Maintenance of Dam.....	4-1
	4.3 Maintenance of Operating Facilities.....	4-1
	4.4 Description of Any Warning System in Effect.....	4-1
	4.5 Evaluation.....	4-1
5	HYDROLOGIC/HYDRAULIC.....	5-1
	5.1 Evaluation of Features.....	5-1
6	STRUCTURAL STABILITY.....	6-1
	6.1 Evaluation of Structural Stability.....	6-1
7	ASSESSMENT, RECOMMENDATIONS & REMEDIAL MEASURES.....	7-1
	7.1 Dam Assessment.....	7-1
	7.2 Recommendations.....	7-1
	7.3 Remedial Measures.....	7-2
	7.4 Alternatives.....	7-2

### APPENDICES

	Designation
VISUAL INSPECTION CHECKLIST.....	A
ENGINEERING DATA.....	B
PHOTOGRAPHS.....	C
HYDROLOGIC AND HYDRAULIC COMPUTATIONS.....	D
INFORMATION AS CONTAINED IN THE NATIONAL INVENTORY OF DAMS..	E





Figure 1 - Overview of Paper Mill Dam.



Reprinted by permission of the Department of Resources and Economic Development, Concord, N.H. 03301, and the copyright owners, The National Survey, Chester, VT. 8-17-78.

SCALE IN MILES



MAP BASED ON STATE OF NEW HAMPSHIRE  
OFFICIAL HIGHWAY MAP.

Anderson-Nichols & Co, Inc.		U.S. ARMY ENGINEER DIV. NEW ENGLAND	
CONCORD		CORPS OF ENGINEERS	
NEW HAMPSHIRE		WALTHAM, MASS.	
NATIONAL PROGRAM OF INSPECTION OF NON-FED. DAMS			
PAPER MILL DAM			
LOCATION MAP			
CONTOOCOOK RIVER		NEW HAMPSHIRE	
		SCALE: SEE BAR SCALE	
		DATE: FEBRUARY 1979	

NATIONAL DAM INSPECTION PROGRAM  
PHASE I INSPECTION REPORT  
PAPER MILL DAM

SECTION 1  
PROJECT INFORMATION

1.1 General

a. Authority. Public Law 92-367, August 8, 1972 authorized the Secretary of the Army, through the Corps of Engineers, to initiate a National Program of Dam Inspection throughout the United States. The New England Division of the Corps of Engineers has been assigned the responsibility of supervising the inspection of dams within the New England Region. Anderson-Nichols & Company, Inc. has been retained by the New England Division to inspect and report on selected dams in the State of New Hampshire. Authorization and notice to proceed were issued to Anderson-Nichols under a letter of November 20, 1978 from Max B. Scheider, Colonel, Corps of Engineers. Contract No. DACW33-79-C-0009 has been assigned by the Corps of Engineers for this work.

b. Purpose

(1) To perform technical inspection and evaluation of non-Federal dams to identify conditions which threaten the public safety and thus permit correction in a timely manner by non-Federal interests.

(2) To encourage and prepare the States to initiate quickly effective dam safety programs for non-Federal dams.

(3) To update, verify and complete the National Inventory of Dams.

1.2 Description of Project

a. Location. Paper Mill Dam is located in Bennington, New Hampshire. The dam is a run-of-the-river dam spanning the Contoocook River approximately 43 miles above its confluence with the Merrimack River in Concord, New Hampshire. The Contoocook River is a major tributary in the Merrimack River Basin. Paper Mill Dam is shown on U.S.G.S. Quadrangle, Hillsboro, New Hampshire with coordinates approximately at N43°00'24", W71°55'36", Hillsborough County, New Hampshire. (See Location Map page vii.)

h. Design and Construction History. One drawing was disclosed of the Paper Mill Dam and Head Gates. This drawing was done by Aberthaw Construction Company in Boston, Massachusetts and dated August 14, 1922. It shows the existence of a previous dam. The drawing indicates that the existing dam was constructed approximately 5.5 feet downstream of the old dam with its crest at the same elevation as the old dam. No details of the previously existing dam were disclosed. This drawing also shows an ogee spillway. Apparently this downstream face was repaired in 1939 and changed to the present straight face inclined at 45°.

i. Normal Operating Procedures. No written operating procedures were disclosed for Paper Mill Dam. The Contoocook River discharge to the damsite is primarily controlled by the Powder Mill Pond Dam, located approximately 5,600 feet upstream. Before reaching the Paper Mill Dam, the discharge from the Powder Mill Pond also flows over the Monadnock Power Station Dam and the Pierce Power Dam located about 2,100 feet and 1,200 feet upstream, respectively. Monadnock Paper Mills own and control each of these dams. Generally, they operate the Powder Mill Pond Dam to provide sufficient discharge at the Paper Mill Dam for use in power generation and industrial water supply in their paper processing plant.

It is reported that every July the waste gate is opened to release accumulated sediment which has built up behind the dam. This annual opening also permits inspection of the gate and the gate operating facilities.

### 1.3 Pertinent Data

a. Drainage Area. The drainage area consists of 191 square miles (122,240 acres) of gently rolling terrain.

#### b. Discharge at Damsite.

(1) Outlet works - waste gate 8'H x 6'W @ invert elevation 620.6' MSL. Gate capacity at top of dam - 710 cfs @ 631.5' MSL. Three head gates 8'H x 6'W @ invert elevation 620.3' MSL. Capacity is controlled by the turbine capacity which is unknown.

(2) The maximum discharge at damsite - a U.S.G.S. gaging station with a drainage area of 368 square miles is located on the Contoocook River near Henniker, New Hampshire. A maximum discharge of 22,200 cfs was reported at this gaging station during the September 1938 flood. Using this figure, the maximum discharge at damsite can be interpolated to be approximately 12,500 cfs.

- (2) Length of spillway crest pool - 1,140
- (3) Length of flood control pool - not applicable

e. Storage (acre-feet)

- (1) Recreation pool - not applicable
- (2) Flood control pool - not applicable
- (3) Spillway crest pool - 25 (approximate)
- (4) Top of dam - 50 (approximate)
- (5) Test flood pool - 85 (approximate)

f. Reservoir Surface (acres)

- (1) Recreation pool - not applicable
- (2) Flood control pool - not applicable
- (3) Spillway crest - 5 (approximate)
- (4) Test flood pool - 7 (approximate)
- (5) Top of dam - 6 (approximate)

g. Dam

- (1) Type - concrete gravity dam
- (2) Length - 280'
- (3) Height - 19' (structural height)
- (4) Top width - varied
- (5) Side slopes - upstream face is vertical; downstream face of spillway is straight but inclined at 45°.
- (6) Zoning - not applicable
- (7) Impervious core - not applicable
- (8) Cutoff - unknown
- (9) Grout curtain - unknown

## SECTION 2 ENGINEERING DATA

### 2.1 Design

No original design data were disclosed for Paper Mill Dam.

### 2.2 Construction

One drawing prepared by Aberthaw Construction Company, Boston, Massachusetts, was found in the files of the New Hampshire Water Resources Board (NHWRB). This was a drawing of the Paper Mill Dam and Head Gates and was dated August 14, 1922. A copy of this drawing can be seen in Appendix B.

### 2.3 Operation

No written engineering operational data for power and process water operations have been prepared. Oral instructions have been in effect during the history of the operations. These instructions are transmitted from supervisors to subordinates.

### 2.4 Evaluation

a. Availability. Limited engineering data were available for Paper Mill Dam. A search of the files of the NHWRB and direct contact with the owner revealed only a limited amount of recorded information.

b. Adequacy. Because of the limited amount of detailed data available, the final assessments and recommendations of this investigation are based on the visual inspection and hydrologic and hydraulic calculations.

c. Validity. The visual inspection is generally consistent with the 1922 drawing by the Aberthaw Construction Company. An ogee spillway crest is shown on this plan; the visual inspection of this dam shows a straight downstream face angled 45°. This change apparently occurred during repairs in 1939.



An earth dike has been constructed north of the roadway to effectively cut off high water from flowing directly into the canal. The dike is approximately 1.7 feet above the roadway and 9.3 feet above the spillway crest. The dike is approximately 190 feet long and 6 feet high. The top of the dike is 9 to 10 feet wide with side slopes of about 3H:1V. The side slopes are wooded and the exposed portion of the dike near the roadway shows a gravel surface which would be susceptible to erosion during high water conditions. (See Appendix C - Figure 4.)

A 12-inch concrete pipe about 20 feet in length extends through this dike. If water should ever pond behind the dike, some discharge could be passed through the pipe into the canal. The inlet to this pipe contains stoplog slots which would provide a means of controlling flow.

On a return visit to the dam on April 19, 1979 it was observed that a piece of the dam crest (approximately 2 cubic feet) had apparently spalled away near the center of the dam. The depression caused by the spalling is reflected in the water surface passing over the crest. (See Appendix C - Figure 15.)

c. Appurtenant Structures. The outlet works and gate-control structures are located at the north abutment. (See Appendix C - Figure 5.) Significant spalling and erosion of the concrete on the downstream side of the gate structure was noted. The presence of bedrock in the discharge channel immediately downstream of the gate structure would indicate that the abutment is on bedrock, which is consistent with design drawings dated 1922 which show the gate structure to be founded on "ledge."

The waste gate is located adjacent to the north abutment of the spillway. The timber gate is manually operated by a mechanism located directly above the opening. At the time of inspection leakage was noted through the timber gate. (See Appendix C - Figure 6.) The downstream concrete wall to the right of the low-level outlet was noted to have deteriorated and spalled from the base to approximately 2 feet up the wall. (See Appendix C - Figure 7.)

The head gates are located adjacent but perpendicular to the waste gate. The leading edges of the head gate inlet structures have also deteriorated and spalled to a depth of approximately 1 - 3 inches. (See Appendix C - Figure 8.) It appeared that some portion of the gate support structures had been recently repaired. The timber gates were inspected in the raised position and found to be in good

## SECTION 4 OPERATIONAL PROCEDURES

### 4.1 Procedures

Although no written operational procedures have been developed for Paper Mill Dam, Messrs. Gordon Bishop, Chief Engineer and George Edwards, Maintenance Superintendent, are fully familiar with the operational procedures of their four dams, Powder Mill, Monadnock Power, Pierce Power, and Paper Mill, and the appurtenant facilities including the operations for hydropower generation. Mr. Bishop maintains complete records of all maintenance performed including cost records and operates on an annual budget. Each summer maximum releases of water from Powder Mill Dam are made and power is generated for a period such that the Powder Mill Reservoir is drawn down to about two feet below the concrete crest. This procedure provides additional storage enabling the lower three ponds to be drawn down for visual inspection and maintenance, if required. The gates at Powder Mill are then closed and the lower three dams are dry for a week to 10 days. This procedure is usually accomplished in July. Accumulated sediment which has built up behind the dam passes downstream through the waste or power gates (waste gate at Paper Mill). The head gates are operated to provide sufficient discharge into the mill building for use in power generation and industrial process water.

### 4.2 Maintenance of Dam

Monadnock Paper Mills is responsible for the maintenance of Paper Mill Dam. No written maintenance program has been prepared. Maintenance is performed as required; larger items are budgeted and scheduled for completion annually. Inspection of the upstream face of the dam is accomplished during the drawdown period. Mill maintenance personnel are aware of spalling and loose concrete in the dam face and funds are approved for repairs to be done in September and October 1979.

### 4.3 Maintenance of Operating Facilities

The annual releasing of sediment through the waste gate enables the testing of the operating facilities to ensure that they are functional.

### 4.4 Description of Any Warning System in Effect

A gage is located on the downstream face of the road crossing located approximately 2,200 feet downstream of Paper Mill Dam. During floodflow periods (usually occurring each spring) when the water reaches 3 feet on this downstream tailwater gage (0' at gage-598' MSL) a flood watch around the clock is initiated by maintenance personnel. Two men ride up and down the road along the stream to observe conditions. Evacuation of the

SECTION 5  
HYDROLOGIC/HYDRAULIC

5.1 Evaluation of Features

a. General. Paper Mill Dam is a low, run-of-the-river concrete gravity dam which impounds a reservoir of small size. The abutments are concrete and would probably withstand considerable overtopping before serious damage would result. The dam has 3.9 feet of freeboard available before overtopping would occur on the north abutment. The south abutment is 4.1 feet above spillway crest. The northerly dike has a crest elevation averaging 9.3 feet above spillway crest.

b. Design Data. No hydrologic or hydraulic design data were disclosed for Paper Mill Dam.

c. Experience Data. Low flow and flood profiles for the March 1936 and September 1938 floods are shown on the Contoocook River, New Hampshire Plan and Profile, Sheet 5 of 7, February 1939, Revised February 1951, U.S. Engineer Office, Boston, Massachusetts. (See Appendix B.)

d. Visual Observations. At the time of inspection, no visual evidence was noted of damage to any portions of the concrete structure caused by excessive discharges.

e. Test Flood Analysis. Paper Mill Dam is classified as being small in size having a hydraulic height of 19 feet and a maximum storage capacity of 50 acre-feet. The dam was determined to have a Significant Hazard classification. Using the Recommended Guidelines for Safety Inspection of Dams, the test flood was determined to be 1/4 Probable Maximum Flood (PMF).

Using the 1/4 PMF, the test flood discharge was determined to be 15,760 cfs. The overtopping analysis indicates that the dam would be overtopped by 5.2 feet during the test flood. The maximum spillway capacity at top of dam is 3,830 cfs which is 24 percent of the test flood discharge. However, because both abutments are concrete, they would probably withstand considerable overtopping before damage. The northerly dike has a crest averaging 9.3 feet above spillway crest and would therefore be on the verge of overtopping during the test flood.

f. Dam Failure Analysis. The impact of failure of Paper Mill Dam at normal flow conditions and at top of dam were assessed using the Guidance of Estimating Downstream

SECTION 6  
STRUCTURAL STABILITY

6.1 Evaluation of Structural Stability

a. Visual Observations. The visual examination indicated the following evidence of potential long-term stability problems:

(1) Deterioration and erosion of the concrete in the main dam, particularly along the cold joints and at the non-overflow portion at the south abutment of the dam.

(2) Spalling and erosion of the concrete on the downstream side of the waste gate structure.

b. Design and Construction Data. A drawing dated 1922 shows the plan of the dam and a typical cross section. The cross section shown on this drawing has an ogee downstream face. No construction data were available.

c. Operating Records. No operating records pertinent to the structural stability of the dam were available.

d. Post-Construction Changes. The dam was apparently repaired in 1939, which is apparently the time when the original ogee downstream face was changed to the present straight face inclined at 45°.

e. Seismic Stability. This dam is located in Seismic Zone No. 2 in accordance with recommended Phase I guidelines does not warrant seismic analysis.

### 7.3 Remedial Measures

#### a. Operating and Maintenance Procedures. The owner should:

(1) Remove trees and brush for a distance of 25 feet upstream and downstream of the south abutment.

(2) Visually inspect the dam once a month.

(3) Establish a written surveillance and warning program to follow in the event of emergency conditions.

(4) Engage a Registered Professional Engineer to make a complete technical inspection once every two years.

### 7.4 Alternatives

None.

APPENDIX A  
VISUAL INSPECTION CHECKLIST

VISUAL INSPECTION CHECKLIST  
PARTY ORGANIZATION

PROJECT Paper Mill Dam, N.H.

DATE November 20, 1978

TIME 8:30 AM

WEATHER Clear, cold (40°F)

W.S. ELEV.      U.S.      DN.S.  
                  627.8    618.5

PARTY:

- |                             |                                  |
|-----------------------------|----------------------------------|
| 1. <u>Warren Guinan</u>     | 6. <u>Leslie Williams</u>        |
| 2. <u>Robert Langen</u>     | 7. <u>Harold Wilcox (1/3/79)</u> |
| 3. <u>Stephen Gilman</u>    | 8. <u>John Falcione (1/3/79)</u> |
| 4. <u>Ronald Hirschfeld</u> | 9. _____                         |
| 5. <u>Robert Ojendyk</u>    | 10. _____                        |

PROJECT FEATURE	INSPECTED BY	REMARKS
1. <u>Hydrology/Hydraulics</u>	<u>R. Langen</u>	
2. <u>Structural</u>	<u>S. Gilman</u>	
3. <u>Soils &amp; Geology</u>	<u>R. Hirschfeld</u>	
4. <u>Mechanical</u>	<u>H. Wilcox</u>	
5. _____		
6. _____		
7. _____		
8. _____		
9. _____		
10. _____		

# PERIODIC INSPECTION CHECKLIST

PROJECT Paper Mill Dam, N.H. DATE November 20, 1978  
 PROJECT FEATURE Northern Dike NAME \_\_\_\_\_  
 DISCIPLINE \_\_\_\_\_ NAME \_\_\_\_\_

AREA EVALUATED	CONDITION
<u>DIKE EMBANKMENT</u>	
Crest Elevation	Ranges from 636.6 - 637.7
Current Pool Elevation	Not applicable
Maximum Impoundment to Date	Not applicable
Surface Cracks	None noted
Pavement Condition	Not applicable
Movement or Settlement of Crest	None noted
Lateral Movement	None apparent
Vertical Alignment	Good
Horizontal Alignment	Good
Condition at Abutment and at Concrete Structures	Good at tiein with road abutment on south end
Indications of Movement of Structural Items on Slopes	None visible
Trespassing on Slopes	Foot path visible on dike crest
Sloughing or Erosion of Slopes or Abutments	Slight erosion at south end exposed gravel surface. Slopes wooded.
Rock Slope Protection - Riprap Failures	None
Unusual Movement or Cracking at or Near Toes	None apparent
Unusual Embankment or Downstream Seepage	None apparent
Piping or Boils	None visible
Foundation Drainage Features	None apparent
Toe Drains	None visible
Instrumentation System	None visible
Vegetation	Grassed crest



# PERIODIC INSPECTION CHECKLIST

PROJECT Paper Mill Dam, N.H. DATE November 20, 1978

PROJECT FEATURE Intake Channel & Structure NAME \_\_\_\_\_

DISCIPLINE \_\_\_\_\_ NAME \_\_\_\_\_

AREA EVALUATED	CONDITION
<u>OUTLET WORKS - INTAKE CHANNEL AND INTAKE STRUCTURE</u>	
a. Approach Channel	Contoocook River
Slope Conditions	Good, vertical concrete sidewalls
Bottom Conditions	Not visible beneath pond level
Rock Slides or Falls	None
Log Boom	See below
Debris	Little
Condition of Concrete Lining	Not visible beneath pond level
Drains or Weep Holes	None apparent
b. Intake Structure	
Condition of Concrete	Concrete in good condition; piers have deteriorated and spalled
Stop Logs and Slots	Good
<p>Logboom - at upstream of intake consists of a wood log with vertical boards. This stops floating trash from reaching the intakes. The top log was weathered and in poor condition.</p> <p>Steel trash racks were rusted but in good condition.</p>	

# PERIODIC INSPECTION CHECKLIST

PROJECT Paper Mill Dam, N.H. DATE November 20, 1978

PROJECT FEATURE Control Tower NAME \_\_\_\_\_

DISCIPLINE \_\_\_\_\_ NAME \_\_\_\_\_

AREA EVALUATED	CONDITION
<u>OUTLET WORKS - CONTROL TOWER</u>	
a. Concrete and Structural	
General Condition	Good
Condition of Joints	Good. No evidence of movement
Spalling	1" - 3" on leading edges of gate piers
Visible Reinforcing	None
Rusting or Staining of Concrete	None visible
Any Seepage or Efflorescence	Little on faces of abutments and piers
Joint Alignment	Good
Unusual Seepage or Leaks in Gate Chamber	None
Cracks	Limited to hair line cracks
Rusting or Corrosion of Steel	Only at embedded elements of steel
b. Mechanical and Electrical	
Air Vents	4 wooden sluice gates. Hand operated wheels. Gates are in good condition
Float Wells	Not applicable
Crane Hoist	Not applicable
Elevator	Not applicable
Hydraulic System	Not applicable
Service Gates	Good condition - operating mechanism - good condition
Emergency Gates	Not applicable
Lightning Protection System	Not applicable
Emergency Power System	Not applicable
Wiring and Lighting System	Not applicable

# PERIODIC INSPECTION CHECKLIST

PROJECT Paper Mill Dam, N.H. DATE November 20, 1978

PROJECT FEATURE Outlet Structure & Channel NAME \_\_\_\_\_

DISCIPLINE \_\_\_\_\_ NAME \_\_\_\_\_

AREA EVALUATED	CONDITION
<u>OUTLET WORKS - OUTLET STRUCTURE AND OUTLET CHANNEL</u>	
General Condition of Concrete	Good
Rust or Staining	None visible
Spalling	Significant deterioration of north wall d/s of low-level outlet at base
Erosion or Cavitation	
Visible Reinforcing	None visible
Any Seepage or Efflorescence	None visible
Condition at Joints	No apparent movement
Drain holes	None apparent
Channel	
Loose Rock or Trees Overhanging Channel	Some trees and brush adjacent to channel, which is wide.
Condition of Discharge Channel	Good. One log across channel immediately downstream of low- level outlet.

# PERIODIC INSPECTION CHECKLIST

PROJECT Paper Mill Dam, N.H. DATE November 20, 1978

PROJECT FEATURE Spillway Weir NAME \_\_\_\_\_

DISCIPLINE \_\_\_\_\_ NAME \_\_\_\_\_

AREA EVALUATED	CONDITION
<u>OUTLET WORKS - SPILLWAY WEIR, APPROACH AND DISCHARGE CHANNELS</u>	
a. Approach Channel	Contoocook River
General Condition	Good
Loose Rock Overhanging Channel	None
Trees Overhanging Channel	Some trees and brush adjacent to channel which is wide - not visible beneath pond surface
Floor of Approach Channel	
b. Weir and Training Walls	
General Condition of Concrete	Fair. Weir has surface erosion ½" deep and 2" deep at concrete pour joints.
Rust or Staining	None visible
Spalling	Some spalling on training walls. See note below.
Any Visible Reinforcing	None
Any Seepage or Efflorescence	Some on training walls at hairline cracks
Drain Holes	None apparent
c. Discharge Channel	
General Condition	Good - very rocky
Loose Rock Overhanging Channel	None
Trees Overhanging Channel	Some trees and brush adjacent to channel which is wide.
Floor of Channel	Bedrock, with some large boulder.
Other Obstructions	Four railroad - bridge piers
	Note: Left abutment and training wall has spalled 4" deep. One area on d/s face about 4' below u/s water line has seepage through concrete. D/s face spalled from frost action.

# PERIODIC INSPECTION CHECKLIST

PROJECT Paper Mill Dam, N.H. DATE November 20, 1978

PROJECT FEATURE Service Bridge NAME \_\_\_\_\_

DISCIPLINE \_\_\_\_\_ NAME \_\_\_\_\_

AREA EVALUATED	CONDITION	
<u>OUTLET WORKS - SERVICE BRIDGE</u>	<u>Over low-level outlet</u>	<u>Over Intake &amp; Bar Rack</u>
<p>a. Super Structure</p> <p>Bearings</p> <p>Anchor Bolts</p> <p>Bridge Seat</p> <p>Longitudinal Members</p> <p>Underside of Deck</p> <p>Secondary Bracing</p> <p>Deck</p> <p>Drainage System</p> <p>Railings</p> <p>Expansion Joints</p> <p>Paint</p>	<p>None</p> <p>None</p> <p>None</p> <p>None</p> <p>Good</p> <p>None</p> <p>Conc, good cond.</p> <p>None</p> <p>Steel-little corrosion</p> <p>Fair</p> <p>Fair</p>	<p>None</p> <p>None</p> <p>None</p> <p>None</p> <p>Fair</p> <p>None</p> <p>Some spalling on east end</p> <p>None</p> <p>Steel-good</p> <p>Fair</p> <p>Fair</p>
<p>b. Abutment &amp; Piers</p> <p>General Condition of Concrete</p> <p>Alignment of Abutment</p> <p>Approach to Bridge</p> <p>Condition of Seat &amp; Backwall</p>	<p>Good</p> <p>Good</p> <p>Not applicable</p> <p>Not applicable</p>	<p>Good-Surface laitance gone below water line</p> <p></p> <p>Not applicable</p> <p>Not applicable</p>

PROJECT Paper Mill Dam

DATE November 20, 1978

PROJECT FEATURE Reservoir

NAME R. Langen

AREA EVALUATED	REMARKS
Stability of Shoreline	Good
Sedimentation	Significant
Changes in Watershed Runoff Potential	None
Upstream Hazards	1 restaurant
Downstream Hazards	Monadnock Paper Mill parking lot and maintenance garage; bridge
Alert Facilities	None
Hydrometeorological Gages	None
Operational & Maintenance Regulations	None posted

APPENDIX B  
ENGINEERING DATA

NEW HAMPSHIRE WATER CONTROL COMMISSION  
DATA ON DAMS IN NEW HAMPSHIRE

LOCATION

STATE NO. 23.05

Town Bennington : County Hillsboro

Stream Contoocook

Basin-Primary Merrimack River : Secondary Contoocook River

Local Name

Coordinates—Lat. 43° 00' + 2,200 : Long. 71° 55' + 2,800

GENERAL DATA

Drainage area: Controlled ..... Sq. Mi.: Uncontrolled ..... Sq. Mi.: Total 192 ..... Sq. Mi.

Overall length of dam 279.3 ft.: Date of Construction 1932

Height: Stream bed to highest elev. 12.58 ft.: Max. Structure 8.03 ft.

Cost—Dam : Reservoir

DESCRIPTION 0 Gee Face Concrete

Waste Gates

Type

Number 1 : Size 8 ft. high x 6 ft. wide

Elevation Invert 7.05 : Total Area 48 sq. ft.

Hoist

Waste Gates Conduit

Number : Materials

Size ft.: Length ft.: Area sq. ft.

Embankment

Type

Height—Max. ft.: Min. ft.

Top—Width : Elev. ft.

Slopes—Upstream on : Downstream on

Length—Right of Spillway : Left of Spillway

Spillway

Materials of Construction Concrete

Length—Total ft.: Net 141 ft.

Height of permanent section—max. 8.03 ft.: Min. ft.

Flashboards—Type Removable : Height 2.0 ft.

Elevation—Permanent Crest : Top of Flashboard

Flood Capacity 5250 cfs.: 27 cfs/sq. mi.

Abutments

Materials: Concrete

Freeboard: Max. 15.5 ft.: Min. ft.

Headworks to Power Devel.—(See "Data on Power Development")

OWNER Monadnock Paper Mills—~~Bennington, N.H.~~

REMARKS

Canal 500' to Mill

Tabulation By A. N. & R. L. T. Date October 18, 1938 2/23/42



NEW HAMPSHIRE WATER CONTROL COMMISSION  
DATA ON WATER POWER DEVELOPMENTS IN NEW HAMPSHIRE

LOCATION AT DAM NO. 22.06  
Town Bennington County Hillsboro  
Stream Contoocook  
Basin-Primary Monadnock River Secondary Contoocook River  
Local Name

GENERAL DATA

Head-Max. ft.: Ave. 30'  
Date of Construction 1922 Use of Power Industrial  
Pondage ac. ft.: Storage ac. ft.

DESCRIPTION

Racks

Size of Rack Opening  
Size of Bar Material  
Area: Gross Sq. Ft.: Net sq. ft.

Head Gates

Type  
Number 3 Size 8 ft. high x 6 ft. wide  
Elevation of Invert 7.24 Total Area 48 sq.  
Hoist

Penstock

Number 1 45" Material Rodney Hunt (Rope Drive)  
Size Length 800

Turbines

Number Makers  
Rating HP. per unit Total Capacity 800 H.  
Max. Dement C.F.S., per unit Total C.F.S.

Drive

Type

Generator

Number 1  
Make General Electric D.C. 250 V  
Rating KW., per unit 200; Total Capacity K. W.

Exciter

Number Make  
Rating-per unit Total Capacity K.

OUTPUT—KWHRS

19	:	19
19	:	19
19	:	19
19	:	19
19	:	19

OWNER Monadnock Paper Mills

Tabulation By A A N & R L T Date October 19, 1938 7/23/42

## NEW HAMPSHIRE WATER RESOURCES BOARD

## QUESTIONNAIRE

## WATER POWERS OF NEW HAMPSHIRE

Monadnock Paper Mills  
Bennington  
New Hampshire

Gentlemen:

We maintain in this office a list of the water power installations in New Hampshire. In recent months we have had several inquiries concerning the water power installations in the State and have found that our information is in some cases out of date.

We are, therefore, bringing this information up to date and request your cooperation by filling in the questionnaire below with data on your development, and return it to us in the enclosed stamped envelope.

Very truly yours,

*R. S. Holmgren*  
Richard S. Holmgren

RSH:GMB  
Encl.

Chief Engineer

Dam No. 22.06 : Location: Contoocook River at Bennington


1. Will you please check or correct:

	Our Data	Your Corrections
Drainage Area - Sq.Mi.	192	
Head - feet	30	
Capacity (Total)	800	
Wheel - H.P.		
Generator - K.W.		


2. Is the power plant now in operation? yes
3. If not, is the equipment in operable condition? yes
4. Is the dam in good repair? yes

(Signed) A. F. Bell, Jr.


Date 7/23-42




SEPTEMBER 1936 FLOOD PROFILE



MARCH 1936 FLOOD PROFILE



LOW FLOW PROFILE



FEB 1951 - PROFILE REVISED

148

150

B-5

CONTOOCOOK RIVER-MILES 140 TO 150  
NEW HAMPSHIRE  
PLAN AND PROFILE  
IN 7 SHEETS SHEET NO. 5 SCALE 1"=50'

L. J. ENGLISH OFFICE, BOSTON, MASS. FEBRUARY 1939	
SUBMITTED	APPROVED
ENGINEER	CHIEF OF DIST. SECS.
APPROVED BY C. M. M. F. C.	
CERT. FORM. E. A. 11, 11, 11, 11	
FILE NO. 143. 2	

BRIDGE (U.S. RT. NO. 202)  
DAM-MONADNOCK PAPER CO.  
DAM-PIERCE POWER  
BRIDGE (U.S. RT. NO. 202)  
DAM-MONADNOCK POWER  
DAM-POWDER MILL

146

147

148

Miles above Newburyport Light

## INVENTORY OF DAMS AND WATER POWER DEVELOPMENTS

BASIN	<u>Merrimack</u>	NO.	<u>1</u>	<u>22.06</u>	<u>182</u> P5C
RIVER	<u>Stoosook</u>	MILES FROM	<u>146.3</u>	D.A.SQ.ML	<u>192</u> C
TOWNSHIP	<u>Bearington</u>	OWNER	<u>Merrill</u>	<u>Old Paper Mills</u>	<u>USGS</u>
LOCAL NAME OF DAM					
BUILT	<u>1922</u>	DESCRIPTION	<u>Concrete Gravity</u>		

POND AREA-ACRES	DRAWDOWN-FT.		POND CAPACITY-ACRE-FT.	
HEIGHT-POP TO BED OF STREAM-FT.	12.58		MAX. MIN.	
OVERALL LENGTH OF DAM-FT.	279.3		MAX. FLOOD HEIGHT ABOVE CREST-FT.	
PERMANENT CREST ELEV. U.S.G.S.	627.64		LOCAL GAGE	
TAILWATER ELEV. U.S.G.S.			LOCAL GAGE	
SPILLWAY LENGTHS-FT.	141 WRB.		FREEBOARD-FT. 4.5 WRB. 4.58	
FLASHBOARDS-TYPE, HEIGHT ABOVE CREST	143 AE		2.0 AE	
WASTE GATES-NO.	WIDTH MAX. OPENING		DEPTH SILL BELOW CREST	
1	6.0	8.0	7.05'	Waste
3	6.0	8.0	7.24'	to wheel channel

REMARKS 4 I Maximum High Water 629.64  
Original plans by Abertshaw Co., Boston, Mass.  
P.S. comm. says dam 10' high 2m' long, spillway 150' long  
Condition good.

Assumed  $C = 3.9$

POWER DEVELOPMENT						
UNITS	NO.	RATED HP	HEAD FEET	C.F.S. FULL GATE	KW	MAKE
	1	800 rated	30		200KW	45 Padbury Hunt Horiz. Turb. GE, DC-757V
USE	Power for Paper Mill.					

REMARKS - Surveyed during March 1936 - Flood by W.R.B.  
Maximum head 5.5 ft discharge 10,000 cfs 52 cfs / mi  
Accompanying sketch copied from Army Engineer's Field notes.  
Primary HP 90° of E. line 185.7  
Canal 300' long to mill Information from Mr. Braid, Chief Engi. per

DATE 1925 P.S.C.  
10/4/37

# DAMS AND THEIR LOCATIONS IN TOWN OF BENNINGTON

No.	Location River, Brook, Pond or Lake	Condition Ruins or Operable	Owner Monadnock Paper Mills	Owner's Address Bennington
1.	Powder Mill Dam Lake	Concrete		
2.	Monadnock Power Station Dam River	"	"	"
3.	Pierce Power Station Dam River	"	"	"
4.	Paper Mill Dam River	"	"	"
5.	Three Dams on two brooks Town Water works	Operable	Town of Bennington	
6.				
7.				
8.	Lake George	Non-operable	Monadnock Paper Mills	"

REC'D. 8/21/37

ROUTE	+
INFORM.	
EX. DEPT.	
RECEIVED	
AUG 10	
1937	

*Wm J Pierce*  
*Bennington*



NEW HAMPSHIRE WATER RESOURCES BOARD  
State House Annex  
Concord, N. H.

December 4, 1961

Monadnock Paper Co,  
Bennington, N.H.

Dear Sir:

To bring our records of hydro-electric power installations up to date, we are requesting you to furnish the following information on your generators in use at the present time:


\_\_\_\_\_ reported as \_\_\_\_\_ 160 KW in 1951  
presently using \_\_\_\_\_ KW generators.  
also: \_\_\_\_\_ 240 KW in 1951  
presently using \_\_\_\_\_ KW generators.  
also: \_\_\_\_\_ 420 KW in 1951  
presently using \_\_\_\_\_ KW generators

Monadnock Station 1 - 120 KVA (22.03)  
Pine Station 1 - 220 KVA (22.00)  
1 - 500 KVA  
Mill Water Wheel 1 - 750 KVA (22.06)  
Yours very truly,  
Francis C. Moore  
Civil Engineer

above wheels & generators  
are in good condition and  
produce power when water  
is available.

McBullard  
Power Engineers





## ELEVATION

Anderson-Nichols & Co., Inc.	U.S. ARMY ENGINEER DIV. NEW ENGLAND
CONCORD	CORPS OF ENGINEERS
NEW HAMPSHIRE	WALTHAM, MASS.


NATIONAL PROGRAM OF INSPECTION OF NON-FED. DAMS

## PAPER MILL DAM

CONTOOCCOOK RIVER	NEW HAMPSHIRE
	SCALE: NOT TO SCALE
	DATE: FEBRUARY 1979



APPENDIX C  
PHOTOGRAPHS



Anderson-Nichols & Co., Inc.		U.S. ARMY ENGINEER DIV. NEW ENGLAND	
CONCORD		CORPS OF ENGINEERS	
NEW HAMPSHIRE		WALTHAM, MASS.	
NATIONAL PROGRAM OF INSPECTION OF NON-FED DAMS			
PAPER MILL DAM			
PHOTO INDEX			
CONTOOCCOOK RIVER		NEW HAMPSHIRE	
		SCALE: NOT TO SCALE	
		DATE: FEBRUARY 1979	



Figure 2 - Looking south along the upstream face of the spillway. Note the erosion of the concrete.



Figure 3 - Looking at the south abutment adjacent to the spillway. Note the spalling of the concrete.



Figure 4 - Looking at the upstream face of the northerly dike. Note the gravel crest.



Figure 5 - View of the river mouth from the dike which contains the large stone pile.




Figure 6 - View of the timber trestle in the waste  
duct, looking north to the north  
end of the tunnel.




Figure 7 - View of the deteriorated and spoiled  
surface at the base of the waste duct.



Figure 3 - View of the trash racks and head gates.  
Note the spalling of the piers.




Figure 9 - Looking north at the timber head gates  
and the operating mechanisms.





Figure 10 - View of the canal which feeds discharge into the mill building for use in power generation and process water.



Figure 11 - Looking at the house/restaurant located on the north bank of the approach channel.



Figure 12 - Looking at the railroad bridge located about 200 feet downstream of the dam.



Figure 13 - View of Monadnock Paper Mills located on the east bank of the discharge channel about 1000 feet below the dam.




Figure 14 - View of the upstream face of the road crossing located approximately 2,200 feet downstream of the dam.



Figure 15 - View of the eroded section of the dam crest.

APPENDIX D  
HYDROLOGIC AND HYDRAULIC COMPUTATIONS



**NATIONAL PROGRAM OF INSPECTION  
OF NON-FED. DAMS  
PAPER MILL DAM**


**BENNINGTON, NEW HAMPSHIRE  
REGIONAL VICINITY MAP**

DEPARTMENT OF THE ARMY  
NEW ENGLAND DIVISION, CORPS OF ENGINEERS  
WALTHAM, MASSACHUSETTS

ANDERSON-NICHOLS & CO., INC.

CONCORD, NH

**SCALE IN MILES**



MAP BASED ON U.S.G.S. 1:250,000 SERIES  
TOPOGRAPHIC MAPPING. ALBANY, NY, CT, MA,  
NH, VT, 1956. REV. 1974. BOSTON, MA, NH, CT, RI, ME,  
1956, REV. 1970. PORTLAND, ME, NH, 1956, REV. 1972  
GLEN FALLS, NY, VT, NH, 1956, REV. 1972.

c/11

Determine discharge rating curve for the dam using the weir equation  $Q = CLH^{3/2}$ , where the 'c' for the dam spillway crest is 3.5\*, 'c' over abutments is 3.2, and 'c' over dike at right abutment 2.8. (Assuming no tailwater)

Trial #1 @ 627.60 Spillway Crest  
 $Q = 0 \text{ cfs}$

Trial #2 @ 628.0  
 $Q = 3.5(142)(0.4)^{3/2} = 126 \text{ cfs}$

Trial #3 @ 629.0  
 $Q = 3.5(142)(1.4)^{3/2} = 823 \text{ cfs}$

Trial #4 @ 630.0  
 $Q = 3.5(142)(2.4)^{3/2} = 1848 \text{ cfs}$

Trial #5 @ 631.5 maximum pool (right abut.)  
 $Q = 3.5(142)(3.9)^{3/2} = 3828 \text{ cfs}$

Trial #6 @ 631.7 left lower abutment  
 $Q = 3.5(142)(4.1)^{3/2} + 3.2(7.8)(0.2)^{3/2}$   
 $= 4126 + 2 = 4128 \text{ cfs}$

Trial #7 @ 633.0  
 $Q = 3.5(142)(5.4)^{3/2} + 3.2(7.8)(1.5)^{3/2} + 3.2(35)(1.3)^{3/2}$   
 $= 6237 + 46 + 166 = 6449 \text{ cfs}$

Trial #8 @ 635.0  
 $Q = 3.5(142)(7.4)^{3/2} + 3.2(7.8)(3.5)^{3/2} + 3.2(35)(3.3)^{3/2}$   
 $= 10,005 + 163 + 671 = 10,839 \text{ cfs}$

\* King & Brater - Figure 5-16, Table 5-13

Trial #9 @ 636.6 low pt. right dike

$$\begin{aligned}
 Q &= 3.5(142)(9.0)^{3/2} + 3.2(7.8)(5.1)^{3/2} + \\
 &\quad 3.2(35)(4.9)^{3/2} + 3.2(4.5)(1.3)^{3/2} + \\
 &\quad 3.2(38)(1.4)^{3/2} + 3.2(25)(1.36)^{3/2} \\
 &= 13419 + 287 + 1215 + 21 + 201 + 129 \\
 &= \underline{15,272 \text{ cfs}}
 \end{aligned}$$

Trial #10 @ 637.0 Stone wall

$$\begin{aligned}
 Q &= 3.5(142)(9.4)^{3/2} + 3.2(7.8)(5.5)^{3/2} + \\
 &\quad 3.2(35)(5.3)^{3/2} + 3.2(3.0)(0.74)^{3/2} + \\
 &\quad 3.2(7.8)(5.5)^{3/2} + 3.2(38)(1.8)^{3/2} + \\
 &\quad 3.2(25)(1.76)^{3/2} + 2.8(170)(0.3)^{3/2} \\
 &= 14,323 + 322 + 1367 + 6 + 322 + \\
 &\quad 294 + 187 + 78 \\
 &= \underline{16,900 \text{ cfs}}
 \end{aligned}$$

Use the above trials to develop  
a discharge rating curve for  
Paper Mill Dam.

4/11

Monadnock Paper Mill Dam  
Discharge Rating Curve  
2/5/79 LWW

DISCHARGE IN CFS

Spillway Crest

627.6

226

528

6230

622

175

6254

18000

MS

623

62



## Paper Mill Dam

BREACH ANALYSIS - to determine downstream hazard classification. Do breach first at normal flow conditions using Mean Annual Flow. Using Water Resources Data for New

Hampshire and Vermont, Water Year

1976, U.S. Geological Survey Water-Data Report NH-VT-76-1 August 1977:

At gage stations on Contoocook River

DA @ 68.1 mi<sup>2</sup> - MAF = 144 cfs or 2.11 csm

DA @ 368 mi<sup>2</sup> - MAF = 858 cfs or 2.33 csm

Due to upstream storage of Powder Mill Pond, a 2.33 csm value is applied to the

DA @ Paper Mill Dam (DA = 191 mi<sup>2</sup>)

∴ Normal Flow Conditions (MAF) =  $191 \times 2.33 = 445$  cfs  
this corresponds to 0.9' depth over spillway.

$$Q_{p1} = \frac{8}{27} W_b \sqrt{g} Y_0^{3/2}$$

$W_b$  = breach width

$g = 32.2$  ft/sec<sup>2</sup>

$Y_0$  = Pool elev. - up river bed

628.5' or 0.9' over spillway crest. Upstream river bed shown on plans = 619.

@ Paper Mill Dam

$$W_b = 142 \times 0.4 = 56.8' \approx 57'$$

$$Y_0 = 628.5 - 619 = 9.5$$

BREACH @ NORMAL FLOW

From above equation:  $Q = 2806$  cfs

$Q$  over dam other than breached area:

$$Q = 3.5 \times 85 \times 0.9^{3/2} = 254 \text{ cfs}$$

Total Breach  $Q$  (normal) =  $2806 + 254 =$

3060 cfs

Use a typical cross section along the downstream reach from the dam to the road crossing at Monadnock Mills and establish a rating curve using the following Mannings Equation:

$$Q = \frac{1.49}{n} \cdot A \cdot R^{2/3} \cdot S^{1/2}$$

$n$  = composite 'n' value

$A$  = area of section ( $\text{ft}^2$ )

$R$  =  $A/WP$  (wetted perimeter)

$S$  = slope of reach

Length of reach = 2400'

Elev. @ d/s toe = 617

Elev. @ end reach = 600

Slope = 0.007

Composite 'n' = 0.09

Trial #1 Assume stage of 5'

Area trapezoid =  $\frac{1}{2}$  height (base 1 + base 2)

$$\text{Area} = \frac{1}{2} \cdot 5 (100 + 175)$$

$$= 688 \text{ ft}^2$$

$$WP = 100 + 25 + 50 = 175$$

$$R = \frac{688}{175} = 3.93$$

$$Q = \frac{1.49}{0.09} \cdot 688 \cdot 3.93^{2/3} \cdot .007^{1/2}$$

$$Q = \underline{2384 \text{ cfs}}$$

7/11

Trial #2 Assume stage of 10'

$$\text{Area} = \frac{1}{2} 10 (100 + 250) \\ = 1750 \text{ ft}^2$$

$$\text{WP} = 100 + 51 + 100 = 251$$

$$R = \frac{1750}{251} = 6.972$$

$$Q = \frac{1.49}{.09} \cdot 1750 \cdot 6.972^{2/3} \cdot .007^{1/2}$$

$$Q = \underline{8903 \text{ cfs}}$$

Trial #3 Assume stage of 3'

$$\text{Area} = \frac{1}{2} 3 (100 + 145) \\ = 367.5$$

$$\text{WP} = 100 + 15 + 30 = 145$$

$$R = \frac{367.5}{145} = 2.5345$$

$$Q = \frac{1.49}{.09} \cdot 367.5 \cdot 2.5345^{2/3} \cdot .007^{1/2}$$

$$Q = \underline{949 \text{ cfs}}$$

Trial #4 Assume stage of 7'

$$\text{Area} = \frac{1}{2} 7 (100 + 205) \\ = 1067.5 \text{ ft}^2$$

$$\text{WP} = 100 + 36 + 70 = 206$$

$$R = \frac{1067.5}{206} = 5.182$$

$$Q = \frac{1.49}{.09} \cdot 1067.5 \cdot 5.182^{2/3} \cdot .007^{1/2}$$

$$= \underline{4452 \text{ cfs}}$$

Use the above trials to establish a downstream x-section rating curve.

8/11

Total Breach Q = 3060 cfs  
Stage = 5.7 feet

Antecedent discharge =  
 $3.5 \cdot 142 \cdot 0.9^{3/2} = 424$  cfs  
Stage = 1.7 feet

∴ Increase in stage caused by  
breach @ normal flow would be  $\approx 4$  feet.

Breach @ top of dam - 631.5' MSL

$$Q_{p1} = \frac{8}{27} W b \sqrt{g} Y_0^{3/2}$$

$$= \frac{8}{27} \cdot 57 \cdot \sqrt{32.2} \times 12.5^{3/2}$$

$$= 4236 \text{ cfs}$$

Q over dam other than breached area:

$$Q = CLH^{3/2}$$

$$= 3.5 \cdot 85 \cdot 3.9^{3/2}$$

$$= 2291 \text{ cfs}$$


Total breach Q = 6527 cfs


Stage @ 6527 = 8.5 feet

Antecedent discharge = 3828 cfs = stage 6.2 feet

∴ Increase in stage caused by breach  
@ top of dam would be 2.3 feet.

CONCLUSIONS: Breach at top of dam would produce the worst downstream damage. The breach at normal flow conditions would stay in bank. Because of the already high tailwater conditions at flow at top of dam and then the increase in stage at breach, this would produce the greater damage. Loss of life would be few, if any. Appreciable property damage would occur to the maintenance garage and parking lot just downstream.





10/11

Paper Mill Dam

D/S Hazard Typical Section

2/5/79 LW

50  
40  
30  
20  
10  
0  
10  
20  
30  
40

40

30

D-11 20

10

0

## GATE CAPACITIES

Determine approximate gate capacities  
at top of dam - 621.5' MSL

### Waste Gate

6' W x 8' H

Invert - 620.6' MSL

Centerline - 624.6' MSL

$$Q = CA\sqrt{2gh} \quad \text{ORIFICE EQUATION}$$

$$Q = (0.7)(48)(\sqrt{64.4 \cdot 6.9})$$

$$Q = 708 \approx \underline{710 \text{ cfs}}$$

### Head Gates

The capacity of the head gates  
is controlled by the turbine  
capacity in the plant which  
is unknown.

APPENDIX E

INFORMATION AS  
CONTAINED IN THE NATIONAL  
INVENTORY OF DAMS



# INVENTORY OF DAMS IN THE UNITED STATES

STATE	FEDERAL DISTRICT	COUNTY	DISTRICT	CONGR. DIST.	NAME	LATITUDE		LONGITUDE		REPORT DATE	
						(N)	(E)	(W)	(S)	DAY	MO
CA	11	02			PAVIL DAM	38 00.0	122 00.0	122 00.0	122 00.0	122 00.0	122 00.0

POPULAR NAME	NAME OF IMPOUNDMENT
	CONTOONCOOK RIVER

REGION	RIVER OR STREAM	NEAREST DOWNSTREAM CITY-TOWN-VILLAGE	POPULATION
CA	CONTOONCOOK	HEPATIC	659

TYPE OF DAM	YEAR COMPLETED	PURPOSES	STRUCT. HEIGHT (FT.)	HYDRAU. HEAD (FT.)	IMPOUNDING CAPACITIES		DIST. FROM DAM (MI.)
					(ACRES-FT.)	(ACRES-FT.)	
CA	1922	MS	10	15	50	25	0

REMARKS											
1. 1922-1923 21-10-10 21-10-10 21-10-10 21-10-10 21-10-10 21-10-10 21-10-10 21-10-10 21-10-10 21-10-10 21-10-10											

DRAINAGE AREA (SQ. MI.)	SPILLWAY TYPE	MAXIMUM DISCHARGE (CFS)	VOLUME OF DAM (CU. YD.)	POWER CAPACITY (KW)	INSTALLED PROPOSED	LENGTH OF DAM (FT.)	WIDTH OF DAM (FT.)	HEIGHT OF DAM (FT.)	LENGTH OF DAM (FT.)	WIDTH OF DAM (FT.)	HEIGHT OF DAM (FT.)
20	1	100	100	100	100	100	100	100	100	100	100

OWNER	ENGINEERING BY	CONSTRUCTION BY
CONTOONCOOK RIVER	CONTOONCOOK RIVER	CONTOONCOOK RIVER

REGULATORY AGENCY	
DESIGN	CONSTRUCTION
CONTOONCOOK RIVER	CONTOONCOOK RIVER

INSPECTION BY	INSPECTION DATE	AUTHORITY FOR INSPECTION
CONTOONCOOK RIVER	2011-07-01	PL 92-367

REMARKS	

VIEW/DATE  
SCS A  
N N  
21 FEB 79

**END**

**FILMED**

**8-85**

**DTIC**